Sentri Homes LLC
GC@SentriHomes.com | 681-202-9778

EXCAVATION & SITE WORK AGREEMENT

This Independent Contractor Agreement ("Agreement") is entered into as of _____ ("Effective Date") by and between: Sentri Homes ("Company"), and Mike Hescock ("Contractor"), an individual sole proprietor.

Company and Contractor may be referred to individually as a "Party" and collectively as the "Parties."

Project Site

Eggen Residence — 27 Higley Hill Road, Dover (East Dover), VT 05341

Owner: Peter Eggen (coordinating with David Ostafin)

Scope of Work

Contractor agrees to provide excavation and site work services for the residential construction project at the Project Site, as described below.

- Clear and strip the designated building area, stripping and stockpiling topsoil separately for reuse at final grade.
- Excavate the basement for the new home (approx. 24 ft × 34 ft, full basement depth below frost line), providing adequate working room around the perimeter for the concrete/foundation contractor to form, pour, and waterproof.
- Excavate for the basement bulkhead / exterior stairwell access in the same pass.
- Dig footing trenches to firm, undisturbed bearing soil, level and to the depth shown on the approved plans.
- Prepare the basement floor level and place stone base as needed for the concrete slab.
- Install perimeter foundation drainage (stone and pipe) around the footings.
- Backfill the foundation with suitable drainable material after the foundation has cured and been cleared for backfill by the foundation contractor.
- Prepare the driveway sub-base: approx. 80 ft driveway to the house, including base material.
- Rough grade the site around the house and establish positive drainage away from the foundation; prepare for final hay and seed.
- Haul off and dispose of excess excavated material / spoils not used for backfill.

Excluded from this Agreement (priced and contracted separately):

- Septic system installation — Owner's responsibility; separate agreement.
- Well drilling and water-line trenching — Owner's responsibility; separate agreement.
- Foundation forming, concrete, and waterproofing — by foundation contractor (B&B Forms) unless otherwise stated above.
- Landscaping beyond rough grade and drainage establishment.

Contractor agrees to perform all work in a professional, workmanlike manner consistent with industry standards and in compliance with all applicable federal, state, and local laws, codes, and regulations.

Estimated Completion

The estimated completion time for the initial excavation and site preparation is approximately one (1) week, weather and site conditions permitting. Backfill and final rough grade will be completed on a return mobilization after the foundation has cured and been released for backfill.

Contract Price & Payment Terms

Description	Amount

Excavation & Site Work (per scope above)	$18,150.00
Driveway sub-base	$_____
Total Contract Price	**$**_____

- 50% of the total contract price is due prior to the start of work.
- The remaining 50% is due upon satisfactory completion of the project.
- Company may withhold payment for defective, incomplete, or non-compliant work.
- Contractor is responsible for their own expenses unless otherwise agreed in writing.

No final payment shall be due until Contractor has completed the agreed scope and corrected any deficiencies.

Unforeseen Conditions

This Agreement is based on normal excavation conditions. Should solid rock, ledge, high groundwater, or other unforeseen underground conditions be encountered during excavation, additional time and costs may be required. Any changes to the scope of work or pricing will be discussed and approved in writing by both Parties prior to proceeding. No additional charges for rock or unforeseen conditions shall be incurred without Company's prior written approval.

Independent Contractor Status

- Contractor is engaged as an independent contractor, not as an employee.
- Contractor will receive IRS Form 1099-NEC.
- Contractor is responsible for all federal, state, and local taxes.
- Contractor is not entitled to Company benefits, workers compensation, unemployment insurance, or employee protections.
- Contractor has full control over the manner and means of performing the work, subject to project specifications and deadlines.

Nothing in this Agreement shall be construed to create a partnership, joint venture, or employment relationship.

Licensing & Insurance

Contractor represents and warrants that:

- Contractor holds all required licenses for the jurisdiction in which work is performed.
- Contractor maintains general liability insurance of not less than $1,000,000 per occurrence (or as required by Company).
- Contractor maintains workers' compensation coverage if required by law.
- Contractor shall provide proof of insurance (Certificate of Insurance) upon request, prior to commencing work.

Contractor assumes full responsibility for any injuries to themselves or their crew.

Tools & Equipment

Contractor shall provide their own tools, vehicles, equipment, safety gear, and labor necessary to complete the work unless otherwise stated in writing.

Workmanship Warranty

Contractor agrees to correct any defective workmanship within a reasonable time after written notice.

Indemnification

Contractor agrees to indemnify, defend, and hold harmless Sentri Homes from any claims, damages, losses, liabilities, penalties, or expenses (including attorney's fees) arising out of:

- Contractor's work

- Contractor's negligence
- Injury to persons or property caused by Contractor
- Failure to comply with laws or building codes

Confidentiality

Contractor agrees not to disclose Company pricing, customer information, project details, or business processes to third parties.

Safety & Compliance

Contractor is solely responsible for:

- Jobsite safety
- OSHA compliance
- Crew supervision
- Locating and verifying underground utilities prior to trenching and excavation (Dig Safe / 811 notification)
- Pulling permits if required (unless otherwise specified)

Term & Termination

This Agreement shall remain in effect until the work is completed or otherwise terminated. Either Party may terminate this Agreement at any time with written notice. Company may terminate immediately for:

- Poor workmanship
- Failure to meet deadlines
- Unsafe practices
- Breach of contract

Contractor shall be paid only for satisfactory work completed prior to termination.

Dispute Resolution

Any dispute arising under this Agreement shall first be attempted to be resolved through good faith negotiation. If unresolved, disputes shall be resolved in the State of Vermont, where the work is performed, unless otherwise required by law.

Governing Law

This Agreement shall be governed by the laws of the State of Vermont.

Entire Agreement

This Agreement constitutes the entire understanding between the Parties and supersedes all prior agreements and proposals. Any amendments must be in writing and signed by both Parties.

SIGNATURES

Sentri Homes	**Contractor (Sole Proprietor)**
By: _____	By: _____
Name: Alonso Timpson	Name: Mike Hescock
Title: CFO	Date: _____
Date: _____	SSN / EIN (for 1099 purposes):

Thank you for choosing Sentri Homes.
Contact: GC@sentrihomes.com