SENTRI HOMES LLC

BUILD WITH TRUST.

FIXTURES · Ostafin / Querido Residence

25 Higgley Hill Rd, Dover, VT 05341

FIXTURE, FINISH & MATERIAL SPECIFICATIONS

1,632 SF Finished + 855 SF Full Basement | Total Build Budget: $200,000

Reference: Construction Plans by Dan Scott Designs / Treehouse Log Homes East — Drawings A1 through A5, dated 1/26/2026

About This Document: This guide consolidates every fixture, finish, and material call-out for the Ostafin / Querido residence. Each line is tagged [PLAN] when called out directly on the construction drawings or [N/S] when not specified by the architect — in which case Sentri Homes has selected a cost-effective option consistent with the $200,000 build budget. Allowances are budgeted amounts included in the build contract. Selections at or below the allowance are fully covered. Overages are invoiced as a change order before ordering. All allowances are supply-only unless noted as installed.

1. FLOORING

Category	Specification / Description	Allowance
LVP — Main Living Areas	[N/S] 1st floor living, dining, kitchen, mudroom (~500 SF, mid-grade waterproof LVP)	$1,800
LVP — Bedrooms & Loft	[N/S] BR1 (1st floor) + BR2 + BR3 + loft area (~1,000 SF)	$3,400
Ceramic Tile — Bathrooms	[N/S] 1st & 2nd floor bath floors (~130 SF, 12x12 ceramic)	$1,300
Basement Slab Finish	[PLAN-derived] 4" concrete slab (855 SF) — sealed concrete, no finished flooring	INCL.
FLOORING SUBTOTAL		**$6,500**

2. CABINETRY

Category	Specification / Description	Allowance
Kitchen Cabinets	[N/S] Stock shaker uppers & lowers, ~14 LF per A3 plan, white or natural	$3,400
Kitchen Hardware	[N/S] Pulls and knobs, satin nickel or matte black	$220
1st Floor Bath Vanity	[N/S] 30" single vanity, stock w/ integrated lav	$650
2nd Floor Bath Vanity	[N/S] 36" single vanity, stock	$800
Laundry/Utility Cabinet	[N/S] Basic upper cabinet over washer/dryer area	$350
CABINETRY SUBTOTAL		**$5,420**

3. COUNTERTOPS

Category	Specification / Description	Allowance
Kitchen Countertops	[N/S] Entry-level quartz, ~28 SF	$1,400
1st Floor Bath Counter	[N/S] Cultured marble integrated w/ vanity	INCL.

Category	Specification / Description	Allowance
2nd Floor Bath Counter	[N/S] Cultured marble integrated w/ vanity	INCL.
COUNTERTOPS SUBTOTAL		**$1,400**

4. PLUMBING FIXTURES

Category	Specification / Description	Allowance
Kitchen Faucet	[N/S] Pull-down spray, stainless or matte black	$220
Kitchen Sink	[N/S] Stainless steel undermount, single bowl	$280
1st Floor Bath	[N/S] Tub/shower combo, faucet, showerhead, toilet (per A3 floor plan)	$800
2nd Floor Bath	[N/S] Tub/shower combo, faucet, showerhead, toilet (per A3 floor plan)	$800
Laundry Hookups	[N/S] Washer box & utility connections (per A3 plumbing wall)	$220
Exterior Hose Bibs	[N/S] (2) frost-free hose bibs	$180
PLUMBING FIXTURES SUBTOTAL		**$2,500**

5. LIGHTING FIXTURES

Category	Specification / Description	Allowance
Kitchen Lighting	[N/S] (2) pendants over peninsula + (1) ceiling fixture	$280
Dining Fixture	[N/S] Centered dining fixture	$180
Great Room Lighting	[N/S] Ceiling fan with light + (2) accent fixtures on timber accents	$420
Bedroom Fixtures	[N/S] (3) bedroom ceiling fixtures (BR1, BR2, BR3 per A3)	$330
Bathroom Vanity Lights	[N/S] 1st & 2nd floor bath vanity lights	$200
Exterior Lighting	[N/S] Front porch, back door, side entry (3–4 fixtures)	$280
Recessed Cans	[N/S] ~22 LED recessed lights main floor + loft	$1,100
Stair/Hall Sconces	[N/S] (3) sconces for stair and hallway	$210
LIGHTING SUBTOTAL		**$3,000**

6. INTERIOR & EXTERIOR DOORS

Category	Specification / Description	Allowance
Therma-Tru FC65 Exterior	[PLAN] (1) 3'0 x 6'8 half-light entry door per A3 Door Schedule	$1,100
Therma-Tru Full Lite Exterior	[PLAN] (1) Full-lite exterior door per A3 Door Schedule	$900
Interior 30" Doors	[PLAN] (7) 30" x 80" solid-core 2-panel per A3 Door Schedule	$1,260
Interior 36" Door	[PLAN] (1) 36" x 80" door per A3 Door Schedule	$220

Category	Specification / Description	Allowance
Bi-Fold Closet Doors	[PLAN] (3) 4'0 bi-fold doors per A3 Door Schedule	$540
Door Hardware	[N/S] Passage & privacy sets, satin nickel (11 sets)	$580
INTERIOR & EXTERIOR DOORS SUBTOTAL		**$4,600**

7. WINDOWS & SKYLIGHTS

Category	Specification / Description	Allowance
Andersen TW210410 Double Hung	[PLAN] (10) units, 3'-0⅛" x 5'-0⅞" rough opening, per A3 Window Schedule	$4,400
Andersen CN235 Double Casement	[PLAN] (1) unit, 2'-10¼" x 3'-5⅜", per A3 Window Schedule	$520
Andersen TW2036 Small DH	[PLAN] (2) units, 2'-2⅛" x 3'-0⅞", per A3 Window Schedule	$480
Velux M04 Fixed Skylights	[PLAN] (6) units, 2'-6 1/16" x 4'-6 7/16", per A3 Window Schedule (loft cathedral)	$2,100
Window Trim & Casing	[PLAN-derived] 1x4 trim around all windows per A2 elevations	$600
WINDOWS & SKYLIGHTS SUBTOTAL		**$8,100**

8. EXTERIOR SIDING, TRIM & ROOFING

Category	Specification / Description	Allowance
6" Log Siding	[PLAN] Primary exterior siding per A2 elevations (~1,697 SF wall area per A4 Wall Schedule)	$4,800
Exterior Trim Package	[PLAN] 1x4 trim, 1x6 corner trim, 1x6 fascia, 1x12 soffit w/ vent strip per A2/A5	$1,700
Cultured Stone Facade	[PLAN] 64 SF accent wall per A4 Wall Schedule (location per architect)	$1,500
Exterior Stain	[N/S] 2-coat semi-transparent stain on log siding & trim	$1,500
Standing-Seam Metal Roofing	[PLAN-revised] 26-ga main house + porch (~1,595 SF total), revised from asphalt shingles on plan	$11,000
Ridge Vent + Soffit Vent	[PLAN] Ridge vent + Cor-A-Vent PS400 continuous soffit vent system per A5	$600
Gutters & Downspouts	[N/S] Seamless aluminum gutters & downspouts	$900
EXTERIOR SUBTOTAL		**$22,000**

9. COVERED PORCH

Category	Specification / Description	Allowance
5/4 Azek Composite Decking	[PLAN] 336 SF entry porch decking per A4 Floor Schedule	$3,800
Porch Posts (6x6 P.T.)	[PLAN] 6x6 P.T. posts on standoff bases per A5 section	$700

Category	Specification / Description	Allowance
Porch Railings & Balusters	[N/S] Code-compliant railing system w/ balusters	$1,200
1x8 Wood Ceiling — Porch	[PLAN] Wood ceiling underside (432 SF per A4 Roof Schedule)	$1,200
PORCH SUBTOTAL		**$6,900**

10. TILE & BACKSPLASH

Category	Specification / Description	Allowance
Kitchen Backsplash	[N/S] Subway tile or simple ceramic, ~25 SF	$600
1st Floor Bath Tub Surround	[N/S] Tub/shower wall tile, ~50 SF ceramic	$550
2nd Floor Bath Tub Surround	[N/S] Tub/shower wall tile, ~50 SF ceramic	$550
TILE & BACKSPLASH SUBTOTAL		**$1,700**

11. PAINT, WOOD CEILINGS & WALL FINISHES

Category	Specification / Description	Allowance
Interior Paint — Walls/Ceilings	[N/S] 2-coat builder-grade paint on drywall surfaces	$2,400
Trim & Door Paint	[N/S] All interior trim, baseboards, and doors	$1,000
1x6 Shiplap Ceiling — Great Room	[PLAN] Shiplap ceiling at cathedral per A5 construction section	$2,200
1x8 Wood Ceiling — Interior	[PLAN] Wood ceiling 944 SF per A4 Roof Schedule (select interior areas)	$1,800
Stone Facade Accent Install	[PLAN] Interior side install of 64 SF stone facade per A4 Wall Schedule (if interior)	$650
PAINT & WALL FINISHES SUBTOTAL		**$8,050**

12. INSULATION PACKAGE

Category	Specification / Description	Allowance
Roof — R-38 Rockwool + Polyiso	[PLAN] R-38 Rockwool batts + R-9.6 (1½") foil-face polyiso per A5	$4,200
Exterior Walls — R-21	[PLAN-derived] R-21 Rockwool batts in 2x6 walls (5" SIP & Log assembly)	$2,800
Basement Walls	[PLAN] R-15 Rockwool batts + 2" rigid foam per A5 (moisture-resistant sheetrock face)	$1,900
INSULATION PACKAGE SUBTOTAL		**$8,900**

ALLOWANCE SUMMARY

Category	Allowance
Flooring	$6,500
Cabinetry	$5,420
Countertops	$1,400
Plumbing Fixtures	$2,500
Lighting Fixtures	$3,000
Interior & Exterior Doors	$4,600
Windows & Skylights	$8,100
Exterior Siding, Trim, Stone & Metal Roofing	$22,000
Covered Porch	$6,900
Tile & Backsplash	$1,700
Paint, Wood Ceilings & Wall Finishes	$8,050
Insulation Package	$8,900
TOTAL ALLOWANCES	**$79,070**

PLAN-SPECIFIED MATERIALS (FROM DRAWINGS A1–A5):

• Roof finish revised to standing-seam METAL ROOFING per client direction (architectural plan shows asphalt shingles).

• Roof assembly: 5/8" T&G plywood roof sheathing; 2x12 rafters @ 24" o.c. (main); 2x6 @ 16" o.c. (porch); R-38 Rockwool batts; R-9.6 (1½") foil-face polyiso; 1x6 shiplap interior cathedral ceiling; 1x8 wood ceiling at porch (per A4 Roof Schedule and A5 section).

• Walls: 5" SIP & Log Siding assembly (1,697 SF per A4 Wall Schedule); 6" log siding finish; 1x4 trim, 1x6 fascia & corner trim, 1x12 soffit w/ vent strip; 64 SF cultured stone facade accent per A4.

• Floors: 1st floor — 3/4" T&G plywood subfloor over 2x10 joists @ 16" o.c. (764 SF); 2nd floor / loft — 2x6 T&G decking over 6x8 timber joists @ 24" o.c. (466 SF) per A4 Floor Schedule.

• Foundation: 8" concrete walls 7'-10" tall (~990 SF / 142 CF) per Foundation Schedule; 16" x 10" footings w/ (2) #5 cont. rebar (128 LF); 4" concrete basement slab (855 SF); precast piers to 5'-0" below grade w/ 6" gravel base; 4" perforated pipe to daylight.

• Basement walls (interior side): Moisture-resistant sheetrock + 2x4 studs @ 16" o.c. + R-15 Rockwool batts + 2" rigid foam per A5; (2) 3½" lally columns.

• Timber accents: 8x8 posts, plates, ties & beams; 4x8 posts; 8x10 carry beams; 8x8 ridge beam (great room) per A4 framing plan.

• LVL beams: (4) 1¾" x 9½" ridge w/ Simpson LSTA18 strap ties @ 24" o.c.; (3) 1¾" x 9½" carry beams; (2) 9¼" LVL w/ 2" foam; (3) 9½" LVL.

• Windows/Doors: (10) Andersen TW210410 DH, (1) Andersen CN235 casement, (2) Andersen TW2036, (6) Velux M04 skylights, (1) Therma-Tru FC65, (1) Therma-Tru full lite, (7) 30" interior, (1) 36" interior, (3) 4'0 bi-fold per A3.

• Porch: 6x6 P.T. posts on standoff bases, 2x8 P.T. joist framing, 5/4 Azek composite decking (336 SF), 1x8 wood ceiling underside, standing-seam metal roof, 2x6 T&G secondary deck where shown.

ITEMS NOT SPECIFIED ON PLANS — COST-EFFECTIVE SELECTIONS:

Flooring finish (mid-grade LVP + ceramic tile in baths); kitchen cabinetry (stock shaker w/ entry-level quartz); bath vanities (stock w/ cultured marble integrated tops); interior paint (builder-grade 2-coat); plumbing fixtures and lighting fixtures (builder-grade); HVAC (cold-climate ducted heat pump w/ air handler — see Cost Breakdown); water heater (50-gal electric); kitchen appliances (allowance for range, refrigerator, dishwasher, hood); exterior stain color; gravel driveway. Upgrades to any of these are handled by Change Order before ordering.

Terms & Conditions: All allowances are budgeted estimates based on materials and quantities shown on the construction plans. Final costs depend on product selections from approved vendors. Selections must be finalized per project schedule (typically within 14 days of request). Unused allowances credited at final reconciliation. Items marked [PLAN] are specified by the architect and must match the drawings unless modified by Change Order. Items marked [N/S] (not specified) reflect Sentri Homes' cost-effective default; alternate selections at additional cost handled by Change Order. This document is not a contract — refer to the signed construction agreement for binding terms. | Sentri Homes — Build With Trust.

Generated 2026-05-18 · Sentri Homes · Build with Trust