SENTRI HOMES LLC

BUILD WITH TRUST.

COST · Ostafin / Querido Residence

25 Higgley Hill Rd, Dover, VT 05341

FULL CONSTRUCTION COST BREAKDOWN

3 Bed / 2 Bath / 1,632 SF Finished + 855 SF Full Basement | Stick-Built w/ Timber Frame Accents

Client: David M. Ostafin and Giovani L. Querido | 25 Higgley Hill Rd, Dover, VT 05341

Contractor: Sentri Homes LLC | May 2026

Reference: Construction Plans by Dan Scott Designs / Treehouse Log Homes East — Drawings A1 through A5, dated 1/26/2026

PROJECT TOTAL: $200,000

DIV 1 — GENERAL REQUIREMENTS, PERMITS & SITE WORK

Line Item & Material Spec	Cost
Site Preparation, Clearing & Rough Grading	$4,800
Temporary Utilities, Power Pole & Job Site Setup	$1,800
Project Management & Superintendent	$4,800
Survey, Soil Testing & Engineering	$1,400
Building Permits & Code Review	$1,200
DIVISION SUBTOTAL	**$14,000**

DIV 2 — FOUNDATION SYSTEM & FULL BASEMENT

Line Item & Material Spec	Cost
Excavation for Full Basement (24' x 34' footprint)	$3,200
8" Concrete Foundation Walls, 7'-10" tall (~990 SF / 142 CF concrete)	$8,400
16" x 10" Concrete Footings w/ (2) #5 cont. rebar (128 LF)	$2,200
4" Concrete Basement Slab over 2" compacted sand (855 SF)	$2,400
Precast Concrete Pier Footers — porch & lally locations, to 5'-0" below grade w/ 6" gravel base	$1,400
(2) 3½" Lally Columns (basement carry posts)	$500
Foundation Waterproofing, Filter Fabric & 4" Perf. Pipe to Daylight	$1,600
Washed Stone Gravel Drainage Bed	$1,000
Beam Pockets in Foundation (4"x6"x9½" deep)	$200
DIVISION SUBTOTAL	**$20,900**

DIV 3 — STRUCTURAL FRAMING & BUILDING ENVELOPE

Line Item & Material Spec	Cost
2x6 P.T. Sill Plate w/ ½" Anchor Bolts (24" from corners, 48" o.c.)	$700
Floor System 1st Floor — 2x10 Joists @ 16" o.c., (3) 9½" LVL center beam (764 SF)	$4,200
3/4" T&G Plywood Subfloor (1st floor)	$1,700
Wall Framing — 2x6 studs (5" SIP & Log assembly per Wall Schedule, 1,697 SF)	$5,000
Interior Partitions — 2x4 @ 16" o.c. (3½" partitions, 2,338 SF + 5½" partition 91 SF)	$3,200
Timber Frame Package — 8x8 posts, plates, ties, beams; 4x8 posts; 8x10 carry beams (rough-sawn)	$4,400
8x8 Ridge Beam & post-to-tie connections (great room)	$1,400
2nd Floor System — 6x8 Joists @ 24" o.c. + 2x6 T&G Decking (466 SF)	$4,200
Roof Rafters — 2x12 @ 24" o.c. (main house) + 2x6 @ 16" o.c. (porch)	$3,400
(4) 1¾" x 9½" LVL Ridge Beam w/ Simpson LSTA18 Strap Ties @ 24" o.c.	$1,200
(3) 1¾" x 9½" LVL Carry Beams + (2) 9¼" LVL w/ 2" foam + (2) 2x10 headers	$1,500
5/8" T&G Plywood Roof Sheathing	$1,800
Wall Sheathing & Housewrap (WRB)	$1,900
Rough Framing Labor (1,632 SF + 336 SF porch + basement)	$10,000
Structural Engineering & Stamped Plans	$1,500
26-Ga Standing-Seam METAL ROOFING — main house (1,163 SF)	$8,200
Standing-Seam Metal Roofing — Porch (432 SF combined)	$2,800
Synthetic Roof Underlayment + Ice & Water Shield (eaves/valleys)	$1,100
Ridge Vent + Cor-A-Vent PS400 Continuous Soffit Vent System	$600
Windows — (10) Andersen TW210410 DH, (1) CN235 Casement, (2) TW2036	$5,400
Skylights — (6) Velux M04 Fixed	$2,100
Exterior Doors — (1) Therma-Tru FC65 Half Lite, (1) Therma-Tru Full Lite	$1,200
Roof Insulation — R-38 Rockwool batts + R-9.6 (1½") Foil-Face Polyiso	$4,200
Wall Insulation — R-21 Rockwool batts in exterior walls	$2,800
Basement Wall Insulation — 2" rigid foam + R-15 Rockwool batts	$1,900
Air Sealing & Vapor Barriers	$600
Drywall — Supply, Hang, Tape & Finish (interior partitions)	$3,600
Moisture-Resistant Sheetrock — Basement & Bath Walls	$900
1x6 Shiplap Ceiling — Main House Cathedral Ceiling (per A5)	$2,200
1x8 Wood Ceiling — Porch underside (432 SF) + select interior areas (944 SF)	$2,400
DIVISION SUBTOTAL	**$86,100**

DIV 4 — MECHANICAL / UTILITY CONNECTIONS

Line Item & Material Spec	Cost
Electrical Service, 200A Panel, Meter Base & Grounding	$2,200
Rough & Finish Electrical Labor (1,632 SF + basement)	$4,800
Plumbing Rough-In — DWV system, supply lines, vent stacks to roof	$2,800
Plumbing Finish Labor (2 baths, kitchen, laundry, hose bibs)	$1,800
Water Heater — 50-gal electric	$1,100
HVAC — Cold-climate ducted heat pump w/ air handler (2-ton)	$5,800
Ductwork, Returns & Registers	$1,500
DIVISION SUBTOTAL	**$20,000**

DIV 5 — EXTERIOR FINISHES & PORCH

Line Item & Material Spec	Cost
6" Log Siding Material (~1,697 SF wall area)	$4,800
Log Siding Installation Labor	$2,800
Exterior Trim — 1x4 trim, 1x6 fascia/corner, 1x12 soffit w/ vent strip	$1,700
Stone Facade — 64 SF accent wall per A4 Wall Schedule (cultured stone veneer)	$1,500
Exterior Stain — 2-coat semi-transparent on log siding & trim	$1,500
Covered Porch — 6x6 P.T. posts on standoff bases, 2x8 P.T. framing, railings	$2,400
5/4 Azek Composite Decking — Front Porch (336 SF)	$2,800
Gutters & Downspouts — Seamless aluminum	$900
DIVISION SUBTOTAL	**$18,400**

DIV 6 — INTERIOR FINISHES

Line Item & Material Spec	Cost
Flooring — LVP main living areas + bedrooms (~1,500 SF, mid-grade waterproof LVP)	$3,400
Tile Flooring — Bathrooms (~130 SF ceramic/porcelain)	$900
Kitchen Cabinetry — Stock shaker w/ quartz counters (~14 LF)	$4,400
Bath Vanities & Countertops — (2) stock vanities w/ cultured marble tops	$1,600
Interior Paint — Walls, ceilings, trim (2-coat builder-grade)	$2,800
Interior Doors — (7) 30" + (1) 36" solid-core; (3) 4'0 bi-folds per A3 schedule	$2,000
Door Hardware — Passage/privacy sets, satin nickel (11 sets)	$600
Stair Systems — 1st-to-2nd + basement stair w/ railing	$2,000
Closet Systems — Wire/melamine shelving in 6 closets	$800
DIVISION SUBTOTAL	**$18,500**

DIV 7 — FIXTURES & APPLIANCES

Line Item & Material Spec	Cost
Plumbing Fixtures — Kitchen sink/faucet, (2) toilets, (2) lavs, tub/shower combo, shower trim	$2,600
Kitchen Appliance Allowance — Range, refrigerator, dishwasher, hood	$2,400
Light Fixtures, Recessed Cans & Ceiling Fans (full home + porch)	$1,600
Smoke & CO Detectors (hardwired per code)	$300
DIVISION SUBTOTAL	**$6,900**

DIV 8 — FLATWORK & SITE CONCRETE

Line Item & Material Spec	Cost
Gravel Driveway & Parking Pad (~80 LF crushed stone)	$1,400
Walkway Path to Front Porch	$600
Concrete Entry Pad / Steps	$700
DIVISION SUBTOTAL	**$2,700**

DIV 9 — LANDSCAPING & FINAL GRADE

Line Item & Material Spec	Cost
Final Grading & Drainage Around Foundation	$1,400
Topsoil, Seed & Erosion Control (disturbed area)	$900
DIVISION SUBTOTAL	**$2,300**

GC OVERHEAD, INSURANCE & CONTINGENCY

Line Item & Material Spec	Cost
Builder's Risk Insurance (course of construction)	$1,200
Project Contingency (~1.5%)	$3,000
General Contractor Overhead & Profit (~3%)	$6,000
DIVISION SUBTOTAL	**$10,200**

PROJECT SUMMARY

Line Item & Material Spec	Cost
Div 1 — General Requirements & Site Work	$14,000
Div 2 — Foundation System & Full Basement	$20,900
Div 3 — Structural Framing & Building Envelope	$86,100
Div 4 — Mechanical / Utility Connections	$20,000
Div 5 — Exterior Finishes & Porch	$18,400
Div 6 — Interior Finishes	$18,500
Div 7 — Fixtures & Appliances	$6,900
Div 8 — Flatwork & Site Concrete	$2,700
Div 9 — Landscaping & Final Grade	$2,300

Line Item & Material Spec	Cost
GC Overhead, Insurance & Contingency	$10,200
PROJECT TOTAL	**$200,000**

MATERIAL SPECS HONORED FROM PLANS:

ROOF: 26-ga standing-seam METAL ROOFING (revised from asphalt shingles shown on plans per client direction); 5/8" T&G plywood roof sheathing; 2x12 rafters @ 24" o.c. main / 2x6 @ 16" o.c. porch; R-38 Rockwool batts + R-9.6 (1½") foil-face polyiso; 1x6 shiplap interior ceiling; 1x8 wood ceiling at porch; ridge vent + Cor-A-Vent PS400 continuous soffit vent.

WALLS: 5" SIP & log siding exterior wall assembly (1,697 SF); 6" log siding finish; 1x4 trim, 1x6 fascia & corner trim, 1x12 soffit w/ vent strip; cultured stone facade accent (64 SF) per Wall Schedule; R-21 Rockwool batts in exterior 2x6 walls.

FOUNDATION: 8" concrete walls 7'-10" tall (~990 SF / 142 CF); 16" x 10" footings w/ (2) #5 cont. rebar; 4" concrete basement slab (855 SF) over 2" compacted sand; precast concrete pier footers to 5'-0" below grade with 6" gravel base; 4" perforated pipe to daylight w/ filter fabric & washed stone gravel; ½" anchor bolts 24" from corners, 48" o.c.

BASEMENT WALLS (interior): Moisture-resistant sheetrock over 2x4 studs @ 16" o.c. + R-15 Rockwool batts + 2" rigid foam; (2) 3½" lally columns at center carry line.

FRAMING: 2x10 joists @ 16" o.c. (1st floor); 6x8 timber joists @ 24" o.c. + 2x6 T&G decking (2nd floor / loft); 8x8 posts, plates, ties & beams w/ 8x10 carry beams and 4x8 posts (great room timber accents); 8x8 ridge beam; (4) 1¾" x 9½" LVL ridge beam w/ Simpson LSTA18 strap ties @ 24" o.c.; (3) 1¾" x 9½" LVL carry beams; (2) 9¼" LVL w/ 2" foam; 2x6 P.T. sill plate.

PORCH: 6x6 P.T. posts on standoff bases; 2x8 P.T. framing; 5/4 Azek composite decking (336 SF); 2x6 T&G secondary decking; 1x8 wood ceiling underside; metal roof finish.

WINDOWS & DOORS: (10) Andersen TW210410 double-hung, (1) Andersen CN235 double casement, (2) Andersen TW2036 small DH, (6) Velux M04 fixed skylights; (1) Therma-Tru FC65 half-lite + (1) Therma-Tru full-lite exterior doors; (7) 30" + (1) 36" solid-core interior + (3) 4'0 bi-fold closet doors per A3 schedule.

ITEMS NOT SPECIFIED ON PLANS — COST-EFFECTIVE SELECTIONS ASSUMED:

Flooring (LVP + ceramic tile), kitchen cabinetry (stock shaker w/ quartz), bath vanities (stock w/ cultured marble), interior paint (builder-grade 2-coat), plumbing fixtures (builder-grade), light fixtures (builder-grade), HVAC (cold-climate ducted heat pump), water heater (50-gal electric), kitchen appliances (allowance), driveway (gravel). Upgrades to any of these handled by Change Order.

EXCLUSIONS:

Land acquisition, septic system & well, off-site utility extensions, interior furnishings, window treatments, fencing, detached structures, HOA fees, and any work not specifically described above or in the construction plans.

All pricing is estimated based on current market conditions and the preliminary plans by Dan Scott Designs / Treehouse Log Homes East dated 1/26/2026 (Sheets A1–A5). Final costs are subject to site conditions, material availability, finalized selections, and any approved change orders.

Generated 2026-05-18 · Sentri Homes · Build with Trust